BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

No.BBMP/EE/DD/Ten/01/2013-14, Date:04.07.2013. **ITEM NO: 05**

MODIFIED SCHEDULE-B

NAME OF WORK: Modified schedule b for Providing Cement Concrete Roads at Kammagondanahalli Area in Ward no. 12, in Shettyhalli Sub-Division

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor **R Shivaram**	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed the disposed earth to be leveled neatly after breaking of clods Complete as per specifications	Cum	400.82	74.52	Rupees Seventy Four and Fifty Two Paise Only
2	Providing Granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., Complete as per specifications	Sqm	1472.40	290.13	Rupees Two Hundred Ninety and Thirteen Paise Only
3	Earthwork in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift up to 1.5m, excavated surface levelled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed Complete as per specifications	Cum	230.00	103.33	Rupees One Hundred Three and Thirty Three Paise Only
4	Providing and laying in position plain cement concrete of mix M10 with OPC cement @ 220 kgs, using 40mm and down size graded granite metal coarse aggregates @ 0.892cum and fine aggregate @ 0.465cum machine mixed, concrete laid in layers not exceeding 15cms. Thick, well compacted, in foundation and plinth, cost of all materials, labour, HOM of machinery, curing Complete as per specifications	Cum	172.50	3799.52	Rupees Three Thousand Seven Hundred Ninety Nine and Fifty Two Paise Only

Signature of the Contractor

Executive Engineer

5	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete (RMC) for R.C C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 for raft foundation, column footing, main and secondary beams. Complete as per specifications	Cum	115.00	5188.57	Rupees Five Thousand One Hundred Eighty Eight and Fifty Seven Paise Only
6	Providing & fixing 20 mm thick compressible fibre board in expansion joint complete as per Drawing & Technical Specification. Complete as per specifications	m	20.00	122.20	Rupees One Hundred Twenty Two and Twenty Paise Only
7	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 10 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading Complete as per specifications	Cum	630.82	92.32	Rupees Ninety Two and Thirty Two Paise Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division.